

All tests in this report are executed according to the ISO 9001  
 certified Quality management system of the BBRI

Test Centre  
 Offices  
 Head Office

B-1342 Limelette, avenue P. Holoffe 21  
 B-1932 Sint-Stevens-Woluwe, Lozenberg 7  
 B-1000 Bruxelles, rue du Lombard 42

Tel.: +32 (0)2 655 77 11  
 Tel.: +32 (0)2 716 42 11  
 Tel.: +32 (0)2 502 66 90

### TEST REPORT


<b>Laboratory</b> <b>Air Quality and Ventilation</b>	<b>O/References</b>	DE 633X203 VE 293/3/EN/EXT Page 1/5
---------------------------------------------------------	---------------------	-------------------------------------------

<b>Date of order of the extension</b>	30-06-2014	<b>Samples registration</b>	N-2014-10-012
<b>Date of issue of the report</b>	02-06-2014	<b>Date of reception of samples</b>	07-02-2014
<b>Date of issue of the report</b>	02-06-2014	<b>Date of the test</b>	12-03-2014
<b>Test carried out</b>	Measurement of the casing leakage of a damper or valve		
<b>References</b>	NBN EN 1751:2014 Ventilation for buildings - Air terminal devices - Aerodynamic testing of dampers and valves		

*This test report contains 5 pages and may only be reproduced in its entirety.  
 Each page of the report has been stamped (in red) by the laboratory and initialed by the head of laboratory.  
 The results and findings are only valid for the tested samples.*

- No sample
- Sample(s) subjected to destructive test
- Sample(s) to be removed from our laboratories 30 calendar days after sending of the report, save in the case of a further written request.

In charge of the tests  
 Philippe Voordecker



Head of laboratory  
 Christophe Delmotte, Ir.

## Test procedure

The determination of the casing leakage of a damper or valve is carried out according to NBN EN 1751:2014 «Ventilation for buildings - Air terminal devices - Aerodynamic testing of dampers and valves».


The test installation comprises the following:

- an adjustable air supply incorporating an air flow rate measuring device;
- a pressure measuring device;
- an airtight test duct which supports the damper or valve subject to the test;
- a blanking plate for the damper or valve.

The test is carried out by subjecting the casing of the damper or valve to a pressure of 2000 Pa. The pressure is then lowered in stages. The air flow rate is recorded at each of the pressure stages.

If temperature and barometric pressure are different from the standard conditions (20 °C and 101325 Pa), the measured airflows are corrected accordingly.

Normalized values are determined through a linear regression.



### Key

- 1 to manometer
- 2 sealed joints
- 3 blanking plate

Principle of test installation according to NBN EN 1751:2014



**Description of the sample**  
 Iris damper with a nominal diameter of 200 mm (IRIS 200)

**Date of test:** 12-03-2014

**Measuring devices:**

Platon GTLK

**Calibration:**

22-05-1989

**Organization:**

Platon

Airflow TA460-P

18-06-2013

TSI Airflow

Testo 720 n°5

13-11-2013

CSTC-WTCB

Airflow TA460-P

18-06-2013

TSI Airflow

**Measurement conditions:**

Air temperature

20,6 °C

Barometric pressure

101420 Pa

**Reference casing area:**

Perimeter of the damper

0,628 m

Reference area

0,628 m<sup>2</sup>

**Measured values**

Static pressure $p_s$ (Pa)	Leakage air flow $q_{VL\ meas}$ (l/s)
200	0,009
400	0,014
600	0,018
800	0,023
1000	0,028
1200	0,033
1400	0,035
1600	0,040
1800	0,043
2000	0,047

**Corrected values**

Case leakage air flow $q_{VLCA}$ (l/s.m <sup>2</sup> )
0,015
0,023
0,029
0,037
0,045
0,052
0,056
0,064
0,068
0,074



**Normalized values**

Classification of case leakage: Class C

Static pressure (Pa)	Leakage air flow (l/s)	Flow rate / pressure characteristic
250	0,010	$q = C \Delta p^n$ (l/s)
500	0,017	
1000	0,028	$C = 0,000195$ (l/s. Pa <sup>n</sup> )
1500	0,037	$n = 0,7186$ (-)
2000	0,046	

